

Every connection matters

## Retrofitting Telehouse South

Julian Hennessy Projects Director, Development & Construction, Telehouse Europe



### **About Telehouse**



Established in 1988, Telehouse provides reliable, secure and flexible colocation services, enabling organisations to accelerate speed to market and create business opportunities through fast, efficient and secure interconnections.

**3,000+** customers globally

45+

data centres around the world in more than

20

cities

99.999%

uptime SLA

The primary home of the London Internet Exchange

Access to over

1,000+

connectivity partners

Powered by

100% renewable energy

400,000m<sup>2</sup>

of total floorspace

### **Telehouse South**

Opened in 2022, Telehouse South will provide a maximum of 18MW of IT power on full development. Integrated with the main Docklands campus via a diverse dark fibre network, our new data centre provides access to one of the world's densest networks, with over 1,000 carriers, ISPs and ASPs.

From summer 2024, two additional floors with a total power capacity of 5.4MW will come online, bringing the total building IT power capacity to 7.4MW.

31,000 sqm
688 footprints per floor
600mm x 1,200mm
30MW, up to 2.7MW per floor
1.24 (annualised)
Dual redundant, Diverse route
N+1 Redundancy, 24hr Fuel Storage
Distributed redundancy (2N resilience for customer loads)
N+1 Heat rejection, N+20% on floor CRAH



### **Building Overview**



Every connection matters

11 floors including 6 data hall levels, each offering up to 2.7MW of IT power capacity.



## Location and Connectivity

### TELEHOUSE

Every connection matters

Telehouse Docklands Campus

Dark Fibre Route A

Dark Fibre Route B

Telehouse South

# Sustainability Approach During the **Design Stage**

#### New cooling system including;

- High efficiency free-cooling air cooled chillers
- Annualised PUE of 1.24 vs existing of 1.68
- Improved acoustic levels
- Reduction on Natural Resources

#### New heating system which provided;

- Complete removal of inefficient gas fired equipment from site
- Local waste heat recovery to feed water source heat pump for building heating
- Improved air quality

#### Upgraded Generator Strategy;

- Removal of all existing aged generator sets
- Installation of new high efficiency sets
- Introduction of SCRs
- Introduction of Urea system
- Exploring use of HVO with manufacturers

#### **Overall facility Improvements;**

- Full replacement of façade from level 5 - 8
- Roof Replacement with improved insulation thickness.
- General improved fabric performance.
- Removal of fossil fuels from the main building.
- Strip out of all floors available to remove outdated inefficient equipment.

#### **External Improvements;**

- Improved bunded fuel filling point
- Installation of new fuel interceptor
- Sustainable surface water improvements
- Sustainable travel plan

100% renewable energy



# Sustainability Approach During the Construction Stage



95% construction waste recycling target



Strive for circular economy



Green procurement



Donations to charities from recycled materials



Industry skillset development



Reduction of embodied and on-site carbon



### Carbon Savings from TATA Steel's Pipework: Optemis Carbon Lite



515 tonnes of CO2 saved This equates to 335 direct flights from London to New York



118 average cars off the road in a year



Or heating 234 homes in the UK for a year



To capture of 1 tonne of CO2 emissions, you would need approximately 50 trees to be grown for one year.

Source: Sustainable Travel Organisation

### Level 2 Before & Now





### Level 3 Before & Now







### Level 6 & 7 Before & Now







### Level 9 Before & Now





### **Rooftop Before & Now**







*Every connection matters* 

### **Thank You**

#### **Julian Hennessy**

Telehouse International Corporation, Coriander Avenue, London, E14 2AA E: julian.hennessy@uk.telehouse.net T: +44 (0)7919 148 788 W: www.telehouse.net